



Key:

- · - Site boundary/ hoarding line
- - - Tree Protection Fencing
- - - Vehicular Route
- - - Forklift Route
- - - Safe Pedestrian Route
- Speed bump
- Warning Signs
- Site Office & Welfare
- Material Storage
- Operative & Visitor Parking

Notes:

Site boundaries to be secure at all times.

Contractor to maintain site access throughout works for emergency vehicles.

Drawing to be read in conjunction with proposed site plan (SK)13 and Outline Construction Management Plan.

All areas affected by construction works to be fully reinstated to at least their original condition.

Contractor will be required to provide clear directional signage to ensure deliveries can locate the site via the identified routes.

No works will commence on site until appropriate welfare facilities have been established.

1. Outline Site Logistics Plan
SCALE - 1 : 500@A1

Community Centre, Heelands, Milton Keynes (SK)14revA - Propose Outline Site Logistics Plan

